BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

PK-A

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/04/2018-19 Dated: 17-12-2018

APPROVED TENDER SCHEDULE –'B'

Package-04

Name of Work:- Improvements to roads and drains at Bharathgowda layout and GKVK layout and surrounding areas in Kempegowda ward no - 01 and Improvements to roads and drains at Jayamuninagara and surrounding areas in Kempegowda ward no - 01

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri H V ONKARAPPA	
				Rate	Rate in Words
1	KSRB 2-2.1 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(a) / 2.3.5 SR 2018-19	Cum	1338.40	347.84	Rupees Three Hundred Forty Seven and Paise Eighty Four Only
2	KSRB4.1.3: Providing and laying position plain cement concrete of Mix 1:4:8 with OPC cement @180Kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregtes @ 0.57 cum machine mixed , concrete laid in layers not exeecding 15 cms, thick, well compacted , in foundation , including cost of all materials, Labour , HOM of Machinery, Curing complete as per Specifications. Specifications No. KBS 4.1, 4.2 (P12/4.3). SR 2018-19	Cum	207.68	5935.41	Rupees Five Thousand Nine Hundred Thirty Five and Paise Forty One Only
3	Providing and laying Plain /reinforced cement concrete for side drains wall and bottom thickness 15cm using M20 nominal mix concrete with OPC cement at 300kg with 20mm and down size granite metal coarse aggregate at 0.69 cum and fine aggregate at 0.43 cum machine mixed well compacted for walls at bottom including centring shuttering cost of materials HOM of machineries curing etc.completeexcluding cost of steel as per MORTH specification No.1500,1700,2200 Page No 271 Ite mo 37.59.2 SR 2018-19 (wall and bottom thickness 15cm.	Cum	394.95	7759.54	Rupees Seven Thousand Seven Hundred Fifty Nine and Paise Fifty Four Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri H V ONKARAPPA	
				Rate	Rate in Words
	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. TMT bars Fe 500 KBS 4.6.3 Page No. 18/ Item No. 4.46/ PWD SR 2018-19	Tonne	20.10	82558.30	Rupees Eighty Two Thousand Five Hundred Fifty Eight and Paise Thirty Only
5	Supplying and fixing precast rainforced concrete slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials.(Drain covering slab)	Sqm	913.50	2564.86	Rupees Two Thousand Five Hundred Sixty Four and Paise Eighty Six Only
6	Providing precast slab of 250 mm thick including cost of all materials, labour, curing ,transportation ,loading ,unloading,etc.,complete as per the direction of engineer in charge-	Sqm	84.00	5946.26	Rupees Five Thousand Nine Hundred Forty Six and Paise Twenty Six Only
7	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C 1:2:4 with top and bottom width 114 and 165mm repectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including formwork curing, including, cost of all materials, labour hire charges of machinery, loading unloading, lead and lift, transportation etc, complete. Page No. 27/ Item No. 5.30/ SR 2018-19	No	244.00	474.65	Rupees Four Hundred Seventy Four and Paise Sixty Five Only
8	KSRB 15-19.1 : Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications. Item no 15.80 SR	Sqm	44.00	43.04	Rupees Forty Three and Paise Four Only
9	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 Item no 24.1 SR 2018-19	Sqm	44.00	93.07	Rupees Ninety Three and Paise Seven Only
10	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregate /sand/kaner/ Moorum KSRRB M100-1 Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications MORTH -100/ Chapter 1 (Page No.133/ Item No 17.1) SR 2018-19	Cum	1338.40	96.10	Rupees Ninety Six and Paise Ten Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.